BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

Name Of Work :- Detailed Estimate for Supplying and Fixing Pathway light sintex pole boxes in ward no 3 and 4

Budget Head .....

Division No..... Estimate No. ..... For Rs.= 500000.00

Sl. No.	Description of Work	Qty.	Rate Rs. Ps.	Unit	Amount
1	Supply and Installation / Fixing / Provision of Pole box with HRC Fuse / MCB provision and suitable connector / terminal for 3 Ph / 1 Ph connections with Loop-In & Loop-Out terminals for 10 Sqmm / 25 Sqmm 3.5 C Al/Ar / Cu/Ar Cable and branch out 2.5 Sqmm 2 core Al/Cu PVC Insulated cable, enclosed in a Thermoplastic, Polystyrene enclosure, which should be shock proof, safe, IP65(Weather Proof), rust proof, dust proof, water proof having Internally Embedded Gasket with provision for cable entry through IP65 Thermoplastic, polyamide glands and/or grommets.200mmx200mmx98mm	182	1917.00	Each	348894.00
2	Wiring for lighting/power circuit using one of PVC insulated 1100v grade, multis and Copper conductor single core cable in open or consealed system of wiring.I Group A Materials.1.5 sqmm Page-5/2.3.2	1000	20.50	Mtrs	20500.00
3	Supplying and Fixing of. mm dia class A GI pipe bracket up to 2 Mtrs long bent at suitable angle and fixing to this bracket 1x40/2x40 watts fluorescent tube street light fitting of all capacities to GI or CI or rail or RCC pole / wall using suitable clamps, bolts, and nuts and wiring using suitable capacity wires.Using 25mm dia G.I.Pipe Page-79/14.1.1	99	775.00	Each	76725.00
4	**GST 12% ON item no 1 to 3**				53534.28
5	Misleniuos				346.72
	Total Rs				500000.00

CERTIFICATE

1. The Place was inspected and work is essential
2. The Provision made in the estimate is adequate and are necessary.
3. The Work comes in the BBMP limit and is legitimate charges on the Corporation Funds.
4. The rates in the Estimate is based on AR/2019-20 / , BESCOM SR approved rates

Asst. Engineer (Elec)

Asst. Exe.Engineer (Elec)
Sub-Division No.
Bruhat Bangalore Mahanagara Palike

EXECUTIVE ENGINEER (ELEC)
YELAHANKA DIVISION
BRUHAT BANGALORE MAHANAGARA PALIKE

Administrative Sanction for Rs. 500000=00
RUPEES FIVE LAKHS ONLY
is accorded for PD298 M AND R TO ELECTRICAL INSTALLATION IN PARKS AND GARDENS PLAY
Registered as 38/2019-20 Subject
to conditions contained in
No. BBMP/EE(E)/47/AS/38/2019-20
Dt 18-12-2019

Executive Engineer

TECHNICALLY SANCTIONED FOR Rs. 500000=00
Rupees FIVE LAKHS ONLY
Under PD298 M AND R TO ELECTRICAL INSTALLATION IN PARKS
Registered as 25/2019-20
Subject
enclosed
Dt. 18-12-2019 BBMP/EE(E)/47/AS/38/2019-20
BBMP/EE(E)/47/TS/25/2019-20
Dated 18-12-2019 Sanctioned
500000=00

Executive Engineer